

WILLOWBEND APARTMENT COMPLEX SOUTH ENTRANCE

- PLANT LIST:
 A. 10 DENSIFORMIS YEW 3g
 B. 2 MULTI-TRUNK YAUPON HOLLY 20g
 C. SEDGE GRASS 32'S
 BED SPACE 1: 50
 BED SPACE 2: 30
 QTY: BED SPACE 3: 50
 BED SPACE 4: 50
 BED SPACE 5: 20
 D. 3 MOHAWK VIBURNUM 5g
 E. 11 EVERLOW YEW 3g

- MATERIALS LIST:
 2 LARGE BOULDERS FOR SITTING
 1 SMALL BOULDER
 5 STICKS 4"x20" METAL EDGING
 12 CUBIC YARDS BLUEUM GARDEN MIX
 110 CUBIC FEET PINE COMPOST
 105 BAGS GRADE "A" PINE BARK MULCH
 15 TONS 3/8" OKLAHOMA RIVER ROCK
 2 ROLLS CONTRACTOR GRADE FILTER FABRIC 6'X100'
 1 BOX SOD STAPLES

- DIRECTIONS:
 * ALL PLANT MATERIAL SHOULD BE PLANTED WITH NO LESS THAN 2" OF ROOT BALL EXPOSED ABOVE GRADE
 * ALL PLANT MATERIAL SHOULD BE DEEP WATERED TO INSURE THAT NO AIR POCKETS ARE NEAR ROOT BALL
 * MULCH SHOULD BE LAID AT A DEPTH NO LESS THEN TO 2"
 * NO MULCH OR DIRT SHOULD BE PLACED AROUND BASE OF NEW OR EXISTING TREES
 * ALL AREAS W/ OKLAHOMA RIVER ROCK SHOULD BE DUG OUT NO LESS THEN 2" BELOW GRADE AFTER REMOVAL IS COMPLETE LAY CONTRACTORS' FABRIC USING SOD STAPLES TO KEEP FABRIC FLAT AND TIGHT. PLACE AT LEAST 2" OF OKLAHOMA RIVER ROCK IN ALL AREAS

